EXTRA ITEM RATE LIST

Name of Work: Construction of RCC Drain at doddabommasandra Main road from Najappa Circle to Petrol Bunk in Ward No. 10 (Do abommasandra).

Name of Agency: ri K.B. Alankar, No. 12, MSV Network Road, near Shoba Apartment, Amruthahalli, Sahakaranagara Post, Bangalore - 560092.

Estimated Cost: 1,00,00,000.00

Tender Amount : Rs. 92,48,152.39 Lakhs

Work Order No. BBMP/EE/BTP/WO/199/2020-21 Dated: 01-03-2021.

Sl. No.	Item No.	Description of Work	Unit	Qty	Rate	Amount	Whether the items are alternative to items in tender schedule or whether being an additional item	Wheather the extra items s included in the sanctioned Estimate	How the expenditure due to the extra item is proposed to be met out	Whether the item isincluded in the S.R (Referabce if SR to be given . If not Data Should accompany the EIRL	Remarks
1	E1	Boundry Pillar:- Reinforced cement concrete M-15 grade boundry pillars of standard design as per IRC:25-1967, fixed in position including finishing and lettering but excluding painting complete as per specifications.MORTH Specification No. 806	Mtrs	628.00	526.25	330485.00	Additional Item	No	By over all savings in the work	2018-19 PWD SR Rates	
2	E2	Providing chain link fencing 50mm size of 8 guage properly stretched between existing rectangular poles and fixed with suitable bolts & nuts, the free ends shall be welded to the pole and block pipe at top and bottom as required including cost of all materials, labour, lead and lifts and as per the directions of the Engineer-in-charge of work including two	Sqm	1324.40	795.49	1053546.96	Additional Item	No	By over all savings in the work	2018-19 PWD SR Rates	
		Total				**1384031.96**					

Percentage Excess $\frac{\text{1384031.96}}{\text{Approved Tender Amoun 9248152.39}} \times 100 =$ 14.97%

Assistant Engineer
Ward No. 10

Assistant Executive Engineer
Vidyaranyapura Sub Division
BBMP, Bangalore - 97

Executive Engineer
Byatarayanapura Division
BBMP, Bangalore - 92